

Statia / Station
BUCURESTI VEST
km ex. 67+286
km pr. 66+729

Grup sanitar
propus spre
demolare/
Toilet propose for
demolition



FUNDATIE CONTAINER CE, FUNDATIE
ANTENA GSMR si IMPREJMUIRE/
CE CONTAINER FOUNDATION, GSMR
ANTENNA FOUNDATION and ENCLOSURE

ZONA AMENAJATA DUPA
LUCRARI - NIVELARE TEREN +
INSAMANTARE/
AREA SET UP AFTER WORKS -
LAND LEVELING + SEEDING

ZONA AMENAJATA DUPA
LUCRARI - NIVELARE TEREN +
INSAMANTARE/
AREA SET UP AFTER WORKS -
LAND LEVELING + SEEDING

platforma depozitare
deseuri/waste
platform 3,5x 2 m.

parcare/parking

rastel biciclete/
bicycle rack

carosabil/road

PERON/PLATFORM +0.55 NSS, L=100.00 m, l=3.05 m

PERON/PLATFORM +0.55 NSS, L=200.00 m, l=3.05

COPERTINA/CANOPY
L=15.00 m, l= 3.00m

L=1034.503

PERON/PLATFORM +0.55 NSS, L=200.00 m, l=3.05

COPERTINA/CANOPY
L=15.00 m, l= 3.00m

L=989.503

Linia 1, Lu = ← 862 m / 862 m →

Linia II, Lu = ← 857 m / 857 m →

Linia III, Lu = ← 901 m / 901 m →

Linia 4, Lu = ← 798 m / 786 m →

Linia 5, Lu = ← 686 m / 672 m →

Linia 6, Lu = ← 672 m / 686 m →



ENTITATE CONTRACTANTA
CONTRACTING ENTITY



C.N.C.F. "C.F.R." - S.A.

CONTRACTANT
CONTRACTOR



Asocierea S.C. ISPCF S.A. - S.C. BAICONS IMPEX SRL

	Nume Name	Data Date	Semnatura Signature
Şef Proiect Project Manager	ing. Viorel GORGONETU	11.2024	
Verificat Checked	arh. Mihai - Alexandru Dumitrescu	11.2024	
Proiectat Designed	arh. Stefania Gheorghe	11.2024	

”Modernizarea liniilor şi instalaţiilor din
Complexul Feroviar Bucureşti”
Studiu de fezabilitate

Proiect / Project
38 / 2022

”Modernization lines and installations in the
Bucharest Railway Complex
Feasibility Study

Faza / Phase
S.F.
F.S.

Denumire / Title

Statia Bucuresti Vest - Plan Situatie
Bucuresti Vest Station - Layout plan

Scara / Scale
1:500

Codificare / Codification System

COBU SF ARH DPS 24 01 001 R00

Istoricul reviziilor / Revision History

Rev.	Data/Date	Descriere Modificare / Modification description
1		
2		
3		
4		



Ti