TABLOU TAMPLARIE DIN ALUMINIU
JOINERY BOARD - ALUMINIUM

NR. CRT / No.	VEDERE *VIEW*	DIMENS. GOL *HOLE DIMENSIONS (cm)* / DIM. EXEC. *BUILT UP DIMENSIONS (mm)*	NR.BUCATI PE NIVEL *NUMBER OF PIECES PER LEVEL* P *Ground Floor*	E *1st floor*	SUPRAFATA de DECONTARE *AREA for SETTLEMENT (mp)* PE BUCATA *per PIECE*	TOTAL *TOTAL*	POZITIA IN PLAN *POSITION IN PLAN*	OBS. *NOTES*
0	1	2	3	4	5	6	7	8
FERESTRE EXTERIOARE PE TAMPLARIE DE ALUMINIU, CU GEAM TERMOIZOLANT, CU OCHIURI MOBILE SI FIXE, CU DESCHIDERE INTERIOARA *ALUMINIUM WINDOWS, WITH THERMO-INSULATING GLASS, MOBILE AND FIXED PANES, INSIDE OPENING*								
1		300x290 2980x2880	2	-	8.70	17.40	F1	
2		100x190 980x1880	4	8	1.90	22.80	F2	
3		60x190 580x1880	7	4	1.15	12.65	F3	fereastra cu geam mat se monteaza la grupurile sanitare
4		60x190 580x1880	6	12	1.15	20.70	F4	
5		300x190 2980x1880	2	8	5.70	57.00	F5	
6		300x290 2980x2880	-	1	8.70	8.70	F6	
FERESTRE INTERIOARE FIXE PE TAMPLARIE DIN ALUMINIU SI GEAM ANTIEFRACTIE *INSIDE WINDOW MADE OUT OF ALUMINIUM,SECURED GLASS*								
7		230x220 2280x2180	1	-	5.10	5.10	G1	

NR. CRT / No.	VEDERE *VIEW*	DIMENS. GOL *HOLE DIMENSIONS (cm)* / DIM. EXEC. *BUILT UP DIMENSIONS (mm)*	NR.BUCATI PE NIVEL *NUMBER OF PIECES PER LEVEL* P *Ground Floor*	E *1st floor*	SUPRAFATA de DECONTARE *AREA for SETTLEMENT (mp)* PE BUCATA *per PIECE*	TOTAL *TOTAL*	POZITIA IN PLAN *POSITION IN PLAN*	OBS. *NOTES*
0	1	2	3	4	5	6	7	8
USI EXTERIOARE PE TAMPLARIE DE ALUMINIU, CU GEAM TERMOIZOLANT, IN DOUA CANATE , CU DESCHIDERE EXTERIOARA *ALUMINIUM DOORS, WITH THERMO-INSULATING GLASS, DOUBLE WINGS, OUTSIDE OPENING*								
1		400x300 3980x2980	1	-	12.00	12.00	UF1	
2		300x300 3980x3980	2	-	9.00	18.00	UF2	
3		180x240 1780x2380	4	-	4.40	17.60	UF3	
4		180x300 1780x2980	1	-	5.40	5.40	UF4	
USI EXTERIOARE PE TAMPLARIE DE ALUMINIU, CU GEAM TERMOIZOLANT, INTR-UN CANAT , CU DESCHIDERE INTERIOARA *ALUMINIUM DOORS, WITH THERMO-INSULATING GLASS, ONE WING, INSIDE OPENING*								
5		100x300 980x2980	ST 1 DR -	ST - DR -	3.00	3.00	UF5	
USI EXTERIOARE METALICE , DIN PROFILE DE ALUMINIU , IN 2 CANATE , CU DESCHIDERE EXTERIOARA *OUTSIDE METALLIC DOORS , ALUMINIUM , DOUBLE WINGS, OUTSIDE OPENING*								
6		180x300 1780x2980	1	-	5.40	5.40	UM 1	

NR. CRT / No.	VEDERE *VIEW*	DIMENS. GOL *HOLE DIMENSIONS (cm)* / DIM. EXEC. *BUILT UP DIMENSIONS (mm)*	NR.BUCATI PE NIVEL *NUMBER OF PIECES PER LEVEL* P *Ground Floor*	E *1st floor*	SUPRAFATA de DECONTARE *AREA for SETTLEMENT (mp)* PE BUCATA *per PIECE*	TOTAL *TOTAL*	POZITIA IN PLAN *POSITION IN PLAN*	OBS. *NOTES*
0	1	2	3	4	5	6	7	8
USI INTERIOARE DIN ALUMINIU , INTR-UN CANAT *INSIDE ALUMINIUM DOORS, SINGLE WING*								
1		100x210 100x210	ST 5 DR 5	ST 8 DR 7	2.10	52.50	U1	
2		90x210 90x210	ST 2 DR 2	ST - DR -	1.90	7.60	U2	
3		80x210 80x210	ST 6 DR 4	ST 2 DR 2	1.70	23.80	U3	
4		180x210 180x210	2	-	3.80	7.60	U4	
5		110x210 110x210	ST - DR -	ST - DR 1	2.40	2.40	U5	
6		200x210 200x210	1	-	4.20	4.20	U6	
USI METALICE INTERIOARE, REZISTENTE LA FOC 60MIN *INSIDE METALIC DOORS, FIRE RESISTENT 60 MINUTES*								
7		100x210 100x210	ST 1 DR -	ST - DR -	2.10	2.10	UM 1	

NOTA :

1. Inainte de comandarea tamplariei se vor verifica dimensiunile exacte pentru fiecare gol de tamplarie in parte.
2. Etansarea tamplariei pe contur se va face cu spuma poliuretanica.
3. Geamul termoizolant va fi compus din doua foi 4-16-4 (float clar + LOW-E) si va avea un coeficient de transfer termic minimal de 1,3W/m² R.
4. Detalii de executie a tamplariei din aluminiu se vor intocmi de catre furnizor si vor fi parte componenta a ofertei tehnice.

1. Before ordering the joinery, the exact dimensions for each joinery hole will be checked separately.
2. The joinery will be sealed all along the outline using polyurethane foam.
4. The thermal insulating window will be made of two sheets 4-16-4 (clear float + LOW -E) and will have a minimum heat transfer coefficient of 1,3W /m2R.
5. The detailed design for the aluminum joinery will be drawn up by the supplier and will be part of the technical offer.



CLADIREA STATIEI RACOS
RACOS RAILWAY STATION BUILDING

Index / Index	Data / Date	Modificare / Modification/Revision	Proiectant / Designer	Aprobat Consultant / Approved Consultant	Aprobat CFR / Approved CFR
D					
C					
B					
A					

GUVERNUL ROMANIEI / ROMANIAN GOVERNMENT
PROIECT FINANTAT DE UNIUNEA EUROPEANA / EUROPEAN UNION FINANCED PROJECT

CLIENT / CLIENT: C.N.C.F. "C.F.R." - S.A.

ITALFERR Grandi Stazioni Joint Venture Scarl · OBERMEYER PLANEN + BERATEN GmbH · TECNIC Consulting Engineers

CONSULTANT / CONSULTANT

			Data / Date	Semnătură / Signature
Aprobat / Approved	Şef proiect / Project manager	R. Liuzza	12.2011	
Aprobat / Approved	Coordonator Specialitate I / Speciality Coordinator I	C. Gemboli	12.2011	
Aprobat / Approved	Project Director / Director Proiect	Giuseppe Fioravanti	12.2011	
Verificat / Checked				

SUBCONTRACTANT / SUBCONTRACTOR

Aprobat / Approved	Responsabil Subcontractant / Subcontractant Responsible	A.Stanciu - Directeco	12.2011	
Întocmit / Elaborated	Proiectant / Designer	Stefania Gheorghe	12.2011	

Reabilitarea liniei de cale ferata Brasov - Simeria, parte componentă a coridorului IV Pan European, pentru circulaţia trenurilor cu viteza maximă de 160 km/h, Tronsonul I Brasov - Bighiseara
Rehabilitation of the railway line Brasov - Simeria, component Part of the IV Pan-European Corridor, for the trains circulation with maximum speed of 160 km/h, Section I Brasov - Bighiseara

Proiect/Project: 2004/RO/16/P/PA/003
Faza / Phase: P.Th. / T.D.

Denumire desen / Drawing Title :
CLADIREA STATIEI RACOS – TABLOU TAMPLARIE INTERIOARA SI EXTERIOARA
RACOS RAILWAY STATION BUILDING - EXTERIOR AND INTERIOR JOINERY BOARD

Codificare / Codification System: Scara / Scale 1:50 | LOT / LOT | Nr. / No. 01 / 01

E A 5 1 | 0 1 | C | 1 1 | B B | C C | 0 0 5 | 1 | 0 0 5 | 1