

TABEL FINISAJE - PARTER

FINISHING LIST FOR GROUND FLOOR

NR. CRT.	RISC INCENDIU FIRE RISK	DENUMIRE SPATH ROOM DENOMINATION	SUPRAFATA AREA (mp)	PERIMETRUL PERIMETER (ml)	INALTIME CAMERA HEIGHT	PARDOSELI FLOORS			PERETI WALLS				TAVANE CEILINGS			OBSERVATI NOTES
						GRESIE SANDSTONE	PARCHET PARQUET	PVC LINOLEUM	ZUGRAV. LAV. WASHABLE PAINTINGS	PLACAJ CERAMIC H=1,50m CERAMIC PLATING	FAIANTA H=2,70m FAIANCE PLATING	VOPSITORII ULEI OIL PAINT	DALE PLAFON FALSE CEILING	RIGIDIZ FAIANTA ARMSTRONG TYPE	ZUGRAV. LAV. WASHABLE PAINTINGS	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
1	mediu medium	SALA ACUMULATORI BATTERY ROOM	22.80	19.40	3.50	•						•			•	
2	mic small	HOL HALL	4.35	8.80	3.50	•			•						•	
3	mediu medium	APA DISTILATA DISTILLED WATER	9.70	12.50	3.50	•						•			•	
4	mic small	CENTRALA TERMICA THERMIC UNIT	10.75	14.30	3.50	•			•						•	
5	mic small	GR.SANITAR SANITARY GROUP	9.60	26.40	2.50	•					•		•			
6	mic small	GR.SANIT.HANDICAP WC FOR THE DISABLED	2.90	6.80	2.50	•					•		•			
7	mic small	HOL HALL	20.70	24.50	3.00	•			•	•				•		gresie antiderapanta antiskid tiles
8	mic small	SPATIU COMERCIAL COMMERCIAL AREA	20.80	21.20	3.00	•			•					•		gresie antiderapanta antiskid tiles
9	mic small	CASA SCARII STAIRCASE HALL	14.50	15.80	3.90	•			•							gresie antiderapanta antiskid tiles
10	mic small	HOL HALL	3.50	7.75	2.70	•			•				•			
11	mic small	BUCATARIE KITCHEN	5.50	9.40	2.70	•			•		•				•	faianta doar pe frontul de lucru faience only on the work stand wall
12	mic small	GR. SANIT SANITARY GROUP	2.80	7.20	2.50	•					•		•			
13	mic small	SUFRAGERIE LIVINGROOM	13.25	15.30	2.70		•		•					•		
14	mic small	DORMITOR BEDROOM	15.00	16.00	2.70		•		•					•		
15	mic small	SALA ASTEPTARE WAITING ROOM	30.50	25.50	3.00	•			•	•				•		gresie antiderapanta antiskid tiles
16	mic small	CASA BILETE TICKETING	3.50	7.60	2.50		•		•				•			
17	mic small	VESTIBUL WINDFANG	3.50	7.60	2.50	•			•				•			gresie antiderapanta antiskid tiles
18	mic small	BIROU MISCARE OFFICE	26.25	20.50	3.00		•		•				•			
19	mic small	SALA RELEE TTR TTR RELEY ROOM	15.50	16.20	3.50			•				•			•	
20	mic small	DISTRICT "L6" APATA "L6" APATA DISTRICT	26.00	20.40	3.50			•	•						•	

D					
C					
B					
A					
Indice Index	Data Date	Modificare Modification/Revision	Proiectant Designer	Aprobat Consultant Approved Consultant	Aprobat CFR Approved CFR
		GUVERNUL ROMANIEI ROMANIAN GOVERNMENT		PROIECT FINANȚAT DE UNIUNEA EUROPEANĂ EUROPEAN UNION FINANCED PROJECT	
				C.N.C.F. "C.F.R." - S.A.	
CLIENT / CLIENT					
GRUPPO FERROVIE DELLO STATO Joint Venture leader		PLANEN + BERATEN GmbH		TECNIC Consulting Engineers	
CONSULTANT / CONSULTANT					
Aprobat Approved		Șef proiect Project manager		R. Liuzza	
Aprobat Approved		Coordonator Secțiune 1 Section 1 Coordinator		C. Gambelli	
Verificat Checked		Expert Cheie Checking Expert		Giuseppe Fioravanti	
				Data Date	
				Semnătură Signature	
SUBCONTRACTANT / SUBCONTRACTOR					
Aprobat Approved		Responsabil Subconsultant Subconsultant Responsible		A.Stanciu - Dinulescu	
Intocmit Elaborated		Proiectant Designer		Alexandra Hegedus	
				12.2011	
Reabilitarea liniei de cale ferata Brașov - Simeria, parte componentă a coridorului IV Pan European, pentru circulația trenurilor cu viteză maximă de 160 km/h, Tronsonul : Brașov - Sighișoara Rehabilitation of the railway line Brașov - Simeria, component Part of the IV Pan-European Corridor, for the trains circulation with maximum speed of 160 km/h, Section : Brașov - Sighișoara					
				Proiect/Project 2004/RO/16/P/PA/003	
				Faza / Phase: D.E. / E.D.	
Denumire desen / Drawing Title :					
STATIA C.F. FELDIOARA - CLADIRE DE CALATORI - TABEL FINISAJE PARTER					
RAILWAY STATION FELDIOARA - TRAVELERS BUILDING - FINISHING WORK LIST FOR GROUND FLOOR					
Codificare / Codification System			Scara / Scale		Nr. / No 01 / 01
E A 5 1 0 1 E 0 7 B X C C 0 0 3 1 0 1 6 0					