

STATIA VANATORI CLADIRE CALATORI PASSENGER BUILDING FINISHING WORKS LIST

RAILWAY STATION VANATORI PASSENGER BUILDING FINISHING WORKS LIST

NR. CRT.	RISC INCENDIU FIRE RISK	DENUMIRE SPATII ROOM DENOMINATION	SUPRAFATA AREA(m ²)	PERIMETRUL PERIMETER (m)	INALTIME CAMERA HEIGHT	PARDOSELI FLOORS			PERETI WALLS			TAVANE CEILINGS			OBSERVATII NOTES	
						GRESIE SANDSTONE	PARCHET PARQUET	PVC PVC	PLACAJ CERAMIC CERAMIC PLATING	FAIANTA FAIENCA PLATING	VOPSI TORII ULEI OIL PAINT	DALE PLAFON FALSE CEILING	PLAFON FALS FALSE CEILING	RIGIPI RIGIDS		CASETAT FALSE CEILING
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
01	mic small	HOL MAIN HALL	54.60	34.40	4.00	•	•	•	•	•	•	•	•	•	•	•
02	mic small	SNACK	25.00	20.20	4.00	•	•	•	•	•	•	•	•	•	•	•
03	mic small	DEPOZIT STORAGE ROOM	5.00	10.80	4.00	•	•	•	•	•	•	•	•	•	•	•
04	mic small	HOL HALL	5.60	10.10	4.00	•	•	•	•	•	•	•	•	•	•	•
05	mic small	GS HANDICAP MAMA SI COPILUL TOILET DISABLED & BABY CARE	4.50	8.60	4.00	•	•	•	•	•	•	•	•	•	•	•
06	mic small	WC FEMEI WC WOMEN	3.90	9.80	4.00	•	•	•	•	•	•	•	•	•	•	•
07	mic small	WC BARBATI WC MEN	6.50	14.50	4.00	•	•	•	•	•	•	•	•	•	•	•
08	mic small	HOL HALL	52.00	61.50	4.00	•	•	•	•	•	•	•	•	•	•	•
09	mic small	CASE BILETE TICKET OFFICE	21.40	25.00	4.00	•	•	•	•	•	•	•	•	•	•	•
10	mic small	SEF STATIE STATION CHIEF	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
11	mic small	IDM MOVEMENT OFFICE	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
12	mic small	REPARTITOR DISTRIBUTING FRAME ROOM	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
13	mic small	SALA COMPUTERE SI RELEE COMPUTER AND RELAY ROOM	44.30	28.40	4.00	•	•	•	•	•	•	•	•	•	•	•
14	mic small	CAMERA SCB SCB ROOM	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
15	mic small	HOL HALL	3.80	8.00	4.00	•	•	•	•	•	•	•	•	•	•	•
16	mic small	GS PERSONAL BARBATI WC STAFF MEN	4.20	10.40	4.00	•	•	•	•	•	•	•	•	•	•	•
17	mic small	GS PERSONAL FEMEI WC STAFF WOMEN	4.20	10.40	4.00	•	•	•	•	•	•	•	•	•	•	•
18	mic small	VESTIAR SI DUS PERSONAL LOCKER and SHOWER STAFF	8.10	15.20	4.00	•	•	•	•	•	•	•	•	•	•	•
19	cat ^g D D categ	CENTRALA TERMICA si HIDROFOR THERMAL STATION HYDROFORE	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
20	mic small	ATELIER CED IS WORKSHOP	10.45	14.30	4.00	•	•	•	•	•	•	•	•	•	•	•
21	mic small	TURANT CED IS SHIFTMAN	10.45	14.30	4.00	•	•	•	•	•	•	•	•	•	•	•
22	mediu medium	ACUMULATORI ACCUMULATORS	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
23	mic small	ELECTROALIMENTARE POWER SUPPLY ROOM	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
24	cat ^g D D categ	GRUP ELECTROGEN GENERATOR	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
25	mic small	SALA RELEE TTR TTR RELAY ROOM	21.40	18.60	4.00	•	•	•	•	•	•	•	•	•	•	•
26	mic small	VESTIBUL VESTIBULE	2.70	6.60	4.00	•	•	•	•	•	•	•	•	•	•	•

D																
C																
B																
A																
Indice Index	Data Date	Modificare Modification/Revision	Proiectant Designer	Aprobat Consultant Approved Consultant	Aprobat CFR Approved CFR											



GUVERNUL ROMANIEI
ROMANIAN GOVERNMENT



PROIECT FINANȚAT DE UNIUNEA EUROPEANĂ
EUROPEAN UNION FINANCED PROJECT



C.N.C.F. "C.F.R." - S.A.

CLIENT / CLIENT



GRUPPO FERROVIE DELLO STATO
Joint Venture leader



PLANNEN + BERATEN GmbH



Consulting Engineers



Consulting Engineers

CONSULTANT / CONSULTANT

Aprobat Approved	Șef proiect Project manager	R. Liuzza	DEC. 2011	Semnătură Signature
Aprobat Approved	Coordonator Secțiune 1 Section 1 Coordinator	C. Gambelli	DEC. 2011	
Verificat Checked	Verificator Verifier	Giuseppe Fioravanti	DEC. 2011	

SUBCONTRACTANT / SUBCONTRACTOR

Aprobat Approved	Responsabil Subconsultant Subconsultant Responsible	A. Stanciu - Dinulescu	DEC. 2011	
Intocmit Elaborated	Proiectant Designer	Andrei MIU	DEC. 2011	

Reabilitarea liniei de cale ferata Brașov - Simeria, parte componentă a coridorului IV Pan European, pentru circulația trenurilor cu viteză maximă de 160 km/h,
Tronsoanel : Brașov - Sighișoara
Rehabilitation of the railway line Brașov - Simeria, component Part of the IV Pan-European Corridor, for the trains circulation with maximum speed of 160 km/h,
Section : Brașov - Sighișoara

Proiect/Project
2004/RO/16/P/PA/003

Faza / Phase:
D.E. / E.D.

Denumire desen / Drawing Title :

STATIA VANATORI CLADIRE CALATORI TABLOU FINISAJE
RAILWAY STATION VANATORI PASSENGER BUILDING FINISHING WORKS LIST

Codificare / Codification System

LOT / LOT

Nr. / No
01 / 01

E A 5 1 0 1 E 1 7 B Z C C 0 0 8 1 0 5 2 0