



This drawing is forbidden to be copied, lent or used in other purposes than those previously approved by ARES Lider Company as its owner.
Se interzice copierea, difuzarea, imprumutarea sau utilizarea in alte scopuri, fara permisiunea ARES Lider Company ca proprietar al desenului.

LEGENDA BETOANELOR/CONCRETE LIST

	Beton armat in cuzineti si in bancheta cuzinetilor Reinforced concrete in the cushions and cushions bench C 35/45-CEM I/A-S 52,5-(XC4+XF3+XA2)-A/C=0,50-D _{max} 16-Cl 0,20
	Beton armat in fundatii indirecte(coaloane si radiere) si in elevatii Plain concrete in abutments foundations: C 25/30-CEM H II/A-S 42,5-(XC4+XF3)-A/C=0,50-D _{max} 32-Cl 0,20
	Beton simplu in fundatii si elevatia arilor Simple concrete foundations and elevation in the wings: C 25/30-CEM II/A-S 32,5-(XF1)-A/C=0,50-D _{max} 32-Cl 0,20
	Beton de egalizare Concrete leveling C 25/30-CEM II/A-S 32,5-(XF3)-A/C=0,55-D _{max} 16-Cl 0,20

In cazul in care temperatura in timpul turnarii este scazuta, se vor folosi cimenturile cu rezistenta initiala mare, R si aditivi acceleratori, iar in cazul turnarii pe timp calduros, cimenturile cu rezistenta initiala uzuala, N si aditivi intarziatori (conf.NE 012/2-2010 si tabelului 2 din SR EN 197-1:2002).
When the temperature during the casting is low, cements with high initial resistance, R and accelerating additives shall be used and when it is cast during warm weather, cements with common initial resistance, N and delaying additives shall be used (according to the norm NE 012/2-2010 and table 2 for the SR EN 197-1: 2002).




ATENTIE/ATENTION
Aprovizionarea aparatelor de reazem se va face inaintea executarii cuzinetilor si a banchetei acestora. In cazul in care inaltimea aparatelor de reazem aprovizionate difera fata de cea considerata in proiect se vor modifica inaltimele pe reazem corespunzator cu noile aparate.
The bearing blocks shall be supplied before building the bearings and their seats. In case the height of the supplied bearing blocks differs from that given in the project, the heights on the seats shall be adjusted so as to comply with the new devices.

NOTE:
1. Prezentul plan s-a intocmit in conformitate cu dispozitia generala.
2. Podul corespunde la convosiile de calcul UIC(LM 71 si SW/2).
3. La executie se vor respecta cu strictete prevederile din "Normativ pentru producerea betonului si executarea lucrarilor din beton, beton precomprimat. Partea 1: Producerea betonului", indicativ NE 012/1-2007 si "Normativ pentru producerea betonului si executarea lucrarilor din beton", indicativ NE 012/2-2010, iar verificarea calitatii lucrarilor si receptionarea lor se va face conform normativului C56-1985.
4. Constructia se incadreaza in categoria de importanta B (constructii de importanta deosebita), modelul 1-de asigurare a calitatii si clasa de importanta B, conform HG 766/1997.
5. Proiectul va fi verificat la exigentele A4.2; B2.2; D2.2.

NOTE:
1. This plan has been drawn up according to the general disposition.
2. The bridge corresponds to the UIC determination convoys (LM71 and SW/2).
3. The execution will strictly comply with the provisions of "Practice code for the concrete production and works execution, reinforced and pre-stressed concrete - Part 1: Practice code for concrete production" NE 012/1-2007 and "Practice code for the concrete production and works execution, reinforced and pre-stressed concrete - Part 2: The execution of concrete works." NE 012/2-2010, and the quality and the reception of the works shall be made accordingly to Norm C 56-1985.
4. The construction has been classified in B category of importance (high important constructions), model 1-ensuring the quality and class of importance B according to G.O. 766/97.
5. The project will be checked in order to comply with the A4.2; B2.2; D2.2 requirements.

DETALIU PENTRU PRINDEREA PLACUTELOR P1 DE TIMPAN
DETAIL TO JOIN THE SLABS P1 AT THE TYMPANUM
Scara 1:5



D					
C					
B					
A	12.2011	Revizia 1 1 Revision	Mihai Ady-Nicolae		
Index	Date	Modificare Modification/Revision	Proiectant Designer	Aprobat Consultant Approved Consultant	Aprobat CFR Approved CFR
GUVERNUL ROMANIEI ROMANIAN GOVERNMENT			PROIECT FINANAT DE UNIUNEA EURO EUROPEAN UNION FINANCED PR		

CLIENT / CLIENT

C.N.C.F. "C.F.R." - S.A.

--	--	--	--

CONSULTANT / CONSULTANT		Date	Semn tur
Aprobat	Șef proiect		Signature
Aprobat	Project manager		
Aprobat	Coordonator Sectiune 1		
Aprobat	Section 1 Coordinator		
Verificat	Expert Chief		
Checked	Checking Expert		

SUBCONTRACTANT / SUBCONTRACTOR		Date	Signature
Aprobat	Responsabil Subcontractant		
Aprobat	Subcontractant Responsible		
Elaborat	Proiectant		
Elaborated	Designer		

Reabilitarea liniei de cale ferata Brasov - Simeria, parte component a coridorului IV Pan European, pentru circulatia trenurilor cu viteza maxim de 160 km/h, **Tronsoanel:**
Rehabilitation of the railway line Brasov - Simeria, component Part of the IV Pan-European Corridor, for the trains circulation with maximum speed of 160 km/h,
Section 1: Brasov - Sighisoara

Denumire desen / Drawing Title:
INTERVAL / SECTION CATA-ARCHITATA
Viaduct Km 254+449.803 D=17x30.00m
PLAN COFRAJ CULEE SIGHISOARA / DECKING PLAN ABUTMENT SIGHISOARA

Codificare / Codification System	Scara / Scale	LOT / LOT	Nr. / No
	1:100		01 / 01
E A 5 1	0 1	E	1 4
B B	P V	0 3	3
2	0 0 4	1	