



Listă forme fasonate B500C

Poz.	Buc.	∅ [mm]	Lungime unitară [m]	Calitate oțel	Bare cotate (fără scară)	Lungime totală [m]	Greutate [kg]
1	75	32	6.40	B500		480.00	3030.24
2	75	32	2.70	B500		202.50	1278.38
3	26	25	8.30	B500		215.80	831.69
4	14	25	12.00	B500		168.00	647.47
5	148	16	3.00	B500		444.00	701.08
6	133	16	2.29	B500		304.57	480.92
7	34	16	11.69	B500		397.46	627.59
8	240	10	3.95	B500		948.00	583.97

Greutate totală B500C: 8181.34
Greutate totală x 2 buc. : 8181.34 x 2 = 16362.68 kg

Note:
Planșa curentă se va citi împreună cu plan armare elevație.
Calitate oțel: B500C
Clasă beton: C25/30
Acoperire cu beton: 5 cm

PROIECTANT / DESIGNER / S.C. CONSITRANS S.R.L.	BENEFICIAR / BENEFICIARY: MUNICIPIUL ARAD, MUNICIPIUL ORADEA, CONSILIUL JUDEȚEAN ARAD, CONSILIUL JUDEȚEAN BIHOR CNAIR	FUNCTIA / POSITION: COORDONATOR DE PROIECT / PROJECT MANAGER	NUME / NAME: ing. S. VEACESLAV	SEMNATURA / SIGNATURE:	Titlu plansa / Drawing title: /	REV. / REV.: R00	DATA / DATE: 11.2023	DETALII REVIZIE / REVISION DETAILS: /	PROIECTAT / DESIGNER: Consitrans
					Plan armare radier pila / Pier pile cap reinforcement plan P1	Pod pe DX la km 61+750 peste Canal / Bridge on DX at km 61+750 over water channel	LUCRARI DE POD / BRIDGE WORKS	Cod plansa / Drawing code: CST-0121-PTE-0-DX-02-P38-ARP-01-R00	
INVESTITIA // INVESTMENT: ACTUALIZARE/COMPLETARE/REVIZUIRE (S.F. + P.A.C. + P.O.E + P.T.E.) "DRUM EXPRES ARAD ORADEA"	ACTUALIZATION/COMPLETION (S.F. + P.A.C. + P.O.E + P.T.E.) "EXPRESS ROAD ARAD ORADEA"	SEF PROIECT SPECIALITATE / TEAM LEADER: ing. D. COVELTIR	PROIECTAT / DESIGNER: ing. V. URDAREANU	VERIFICAT / INTERNAL CHECKER: ing. D. COVELTIR	Contract / Contract: 14724/01.07.2021	Data / Date: 11.2023	Scara / Scale: 1:50	UNIUNEA EUROPEANA / EUROPEAN UNION	GOVERNUL ROMANIEI / ROMANIAN GOVERNMENT