

Foraje geotehnice/ Geotechnical borhole
Pasaj pe DE(drum agricol) peste DX la km 66+815 /
Bridge on DE(agricultural road) over DX at km 66+815



Cota fata de:		Level vs:	Stratum thickness	Underground water depth	Stratification	Formatiunea geologica	DENUMIREA STRATULUI (conform Stas 1243-88 si SR EN ISO 14688/2-2018)
0.00	Foraj						
0.00		0.00					
Foraj		Bore-hole (pit)					
		2.00	2.00				Sol vegetal
		3.60	1.60	3.70			Argila prafoasa cafenie deschis, varioasa
		6.60	3.00				Argila cafeniu-galbui, plastica
		9.00	2.40				Argila cafeniu inchisa-cenusie, plastica
		10.60	1.60				Argila prafoasa, albastruie, plastica
		16.80	6.20				Nisip mediu, cenuziu, afanat
		19.00	2.20				Argila, cenuziu-albastruie, plastica
		21.00	2.00				Argila prafoasa, cenuziu-albastruie, plastica
		25.00					Nisip argilos, cenuziu-albastrui, plastic
		25.00					Nisip prafos, cenuziu-albastrui, plastic

Cota fata de:		Level vs:	Stratum thickness	Underground water depth	Stratification	Formatiunea geologica	DENUMIREA STRATULUI (conform Stas 1243-88 si SR EN ISO 14688/2-2018)
0.00	Foraj						
0.00		0.00					
Foraj		Bore-hole (pit)					
		0.30	0.30				Sol vegetal
		1.50	1.20				Argila prafoasa, negricioasa, tare
		8.50	7.00				Pamant fin cu plasticitate mare / Argila grasa, cenusie, plastic varioasa (CI)
		10.40	1.90				Pamant fin cu plasticitate mare / Argila grasa, cenusie-verzuie, plastic varioasa (CI)
		15.00	4.60				Pamant mixt, curba granulometrica neuniforma / Nisip prafos cenuziu
		16.00	1.00				Pamant fin cu plasticitate mare / Argila cenusie, plastic consistenta (SI CI)
		17.00	1.00				Argila cenusie, plastic consistenta
		23.00	6.00				Pamant fin cu plasticitate mare, siab organic / Argila cenusie, plastic consistenta (CI) M.O:2-6
		25.00	2.00				Pamant fin cu plasticitate medie / Argila prafoasa, cenusie, plastic varioasa (SI CI)
		25.00					Pamant fin cu plasticitate medie / Nisip argilos cenuziu, plastic moale (sa si CI)

PROIECTANT / DESIGNER: S.C. CONSITRANS S.R.L.		BENEFICIAR / BENEFICIARY: MUNICIPIUL ARAD, MUNICIPIUL ORADEA, CONSILIUL JUDETEAN ARAD, CONSILIUL JUDETEAN BIHOR CNAIR	FUNCTIA / POSITION: COORDONATOR DE PROIECT / PROJECT MANAGER	NUME / NAME: ing. S. VEACESLAV	SEMNATURA / SIGNATURE: 	Titlu plansa / Drawing title: Foraje geotehnice/ Geotechnical Borhole	REV./ REV.: R00	DATA/ DATE: 11.2023	DETALII REVIZIE / REVISION DETAILS: P.T.E.	PROIECTAT / DESIGNER: Consitrans
		INVESTITIA / INVESTMENT: ACTUALIZARE/COMPLETARE/REVIZUIRE (S.F. + P.A.C. + P.O.E + P.T.E.) "DRUM EXPRES ARAD ORADEA" ACTUALIZATION/COMPLETION (S.F. + P.A.C. + P.O.E + P.T.E.) "EXPRESS ROAD ARAD ORADEA"	SEF PROIECT SPECIALITATE / TEAM LEADER: ing. D. COVELTIR		Pasaj pe DE (drum agricol) peste DX la km 66+815 Bridge on DE (agricultural road) over DX at km 66+815					
		FAZA PROIECTARE / DESIGN STAGE: PROIECT TEHNIC DE EXECUTIE / EXECUTION TECHNICAL PROJECT	PROIECTAT / DESIGNER: ing. V. URDAREANU		LUCRARI DE POD / BRIDGE WORKS					
UNIUNEA EUROPEANA PROIECT CO-FINANAT DIN FONDUL DE COEZIUNE, PRIN PROGRAMUL OPERATIONAL INFRASTRUCTURA MARE / PROJECT CO-FINANCED FROM THE COHESION FUND, THROUGH THE LARGE INFRASTRUCTURE OPERATIONAL PROGRAM	INSTRUMENTE STRUCTURALE 2014-2020	Contract /Contract: 14724/01.07.2021 Data /Date: 11.2023 Scara /Scale: 1:200	VERIFICAT / INTERNAL CHECKER: ing. D. COVELTIR		Cod plansa / Drawing code: CST-0121-PTE-0-DX-02-P38b-DGF-01-R00					