



Listă forme fasonate B500C

Poz.	Buc.	ø [mm]	Lungime unitară [m]	Calitate oțel	Bare cotate (fără scară)	Lungime totală [m]	Greutate [kg]
1	75	32	6.40	B500		480.00	3030.24
2	75	32	2.70	B500		202.50	1278.38
3	26	25	8.30	B500		215.80	831.69
4	14	25	12.00	B500		168.00	647.47
5	148	16	3.00	B500		444.00	701.08
6	133	16	2.29	B500		304.57	480.92
7	34	16	11.69	B500		397.46	627.59
8	240	10	3.95	B500		948.00	583.97

Greutate totală B500C: 8181.34
Greutate totală x 2 buc. : 8181.34 x 2 = 16362.68 kg

Note:
Plasa curentă se va citi împreună cu plan armare elevație.
Calitate oțel: B500C
Clasă beton: C25/30
Acoperire cu beton: 5 cm

PROIECTANT / DESIGNER: S.C. CONSITRANS S.R.L.	BENEFICIAR / BENEFICIARY: MUNIPIUL ARAD, MUNICIPIUL ORADEA, CONSILIUL JUDETEAN ARAD, CONSILIUL JUDETEAN BIHOR CNAIR	FUNCTIA / POSITION: COORDONATOR DE PROIECT / PROJECT MANAGER	NUME / NAME : ing. S. VEACESLAV	SEMNATURA / SIGNATURE: 	Titlu plansa / Drawing title: / Plan armare radier pila / Pier pile cap reinforcement plan P1,P2,P4,P5,P7,P8,P9,P11, P12,P13,P19,P20,P22	REV. / REV.: R00	DATA / DATE: 11.2023	DETALII REVIZIE / REVISION DETAILS: / P.T.E.	PROIECTAT / DESIGNER: Consitrans
	INVESTITIA // INVESTMENT: ACTUALIZARE/COMPLETARE/REVIZUIRE (S.F. + P.A.C. + P.O.E + P.T.E.) "DRUM EXPRES ARAD ORADEA"	SEF PROIECT SPECIALITATE / TEAM LEADER: ing. D. COVELTIR			Pod pe DX la km 71+700 peste Crisul Alb Bridge on DX at km 71+700 over Crisul Alb river				
	FAZA PROIECTARE / DESIGN STAGE: PROIECT TEHNIC DE EXECUTIE / EXECUTION TECHNICAL PROJECT	PROIECTAT / DESIGNER: ing. V. URDAREANU			LUCRARI DE POD / BRIDGE WORKS				
	Contract /Contract: 14724/01.07.2021 Data /Date: 11.2023 Scara /Scale: 1:50	VERIFICAT / INTERNAL CHECKER: ing. D. COVELTIR			Cod plansa / Drawing code : CST-0121-PTE-0-DX-02-P40-ARP-01-R00				

