



Pila	Inalțimi			Cote de nivel					
	H ₁	H ₂	H ₃	A	B	C	D	E	F
Pila 15stg	11.45	12.95	14.95	90.68	90.58	92.58	104.03	105.53	105.58
Pila 17stg	9.95	11.45	13.45	91.31	91.21	93.21	103.16	104.66	104.71
Pila 15dr	11.95	13.45	15.45	90.78	90.68	92.68	104.63	106.13	106.18
Pila 17dr	10.45	11.95	13.95	91.41	91.31	93.31	103.76	105.26	105.31

Materiale							
Beton							
Element	Clasa de rezistență	Clasa de expunere	Raport A/C	Clasa de cloruri	Dozaj ciment [kg]	D _{max} [mm]	Consistență
Beton egalizare	C12/15	X0	-	1.00	-	32	S4
Piloli forati	C25/30	XC2	0.55	0.20	375	22.4	S3
Radiere	C25/30	XC2; XF2	0.55	0.20	300	32	S3
Elevatii	C30/37	XC4; XF4; XD1	0.45	0.20	340	32	S3

PROIECTANT / DESIGNER: S.C. CONSITRANS S.R.L.	BENEFICIAR / BENEFICIARY: MUNICIPIUL ARAD, MUNICIPIUL ORADEA, CONSILIUL JUDETEAN ARAD, CONSILIUL JUDETEAN BIHOR CNAIR	FUNCTIA / POSITION: COORDONATOR DE PROIECT / PROJECT MANAGER	NUME / NAME: ing. S. VEACESLAV	SEMNTATURA / SIGNATURE: 	Titlu plansa / Drawing title: Plan cofraj pila P15, P17	REV/ REV.: R00	DATA/ DATE: 11.2023	DETALII REVIZIE / REVISION DETAILS: PTE	PROIECTAT / DESIGNER: Consitrans
					INVESTITIA / INVESTMENT: ACTUALIZARE/COMPLETARE/REVIZUIRE (S.F. + P.A.C. + P.O.E + P.T.E.) "DRUM EXPRES ARAD ORADEA" ACTUALIZATION/COMPLETION (S.F. + P.A.C. + P.O.E + P.T.E.) "EXPRESS ROAD ARAD ORADEA"	SEF PROIECT SPECIALITATE / TEAM LEADER: ing. D. COVELTIR	Pod pe DX la km 71+700 peste Crisul Alb Bridge on DX at km 71+700 over Crisul Alb river		
	FAZA PROIECTARE / DESIGN STAGE: PROIECT TEHNIC DE EXECUTIE / EXECUTION TECHNICAL PROJECT	PROIECTAT / DESIGNER: ing. V. URDAREANU	VERIFICAT / INTERNAL CHECKER: ing. D. COVELTIR		Pod pe DX la km 71+700 peste Crisul Alb Bridge on DX at km 71+700 over Crisul Alb river				
					Contract /Contract: 14724/01.07.2021	Data / Date: 11.2023	Scara /Scale: 1:100	PROIECTAT / DESIGNER: ing. V. URDAREANU	VERIFICAT / INTERNAL CHECKER: ing. D. COVELTIR